

**WWDS-SL PSLM**

**Procedure for self laying mains**

key	SLP action	Wessex Water action	All parties	<input checked="" type="checkbox"/>
1	Self-lay application submitted by the developer/SLP		Form <b>WWDS-SLM1</b>	<input type="checkbox"/>
2	Design agreed and approved			<input type="checkbox"/>
3	Self-lay agreement prepared and signed by all parties			<input type="checkbox"/>
4	Mains surety non-contestable cost paid			<input type="checkbox"/>
5	Notification of pre-start meeting/meeting held on site			<input type="checkbox"/>
6	Notification of mainlaying commencement and trench self-certification submitted		Form <b>WWDS-SLM2</b>	<input type="checkbox"/>
7	Authorisation to proceed/commence mainlaying			<input type="checkbox"/>
8	SLP lays site mains			<input type="checkbox"/>
9	Notification of proposed mains pressure testing, chlorination and as laid drawings submitted		Form <b>WWDS-SLM3</b>	<input type="checkbox"/>
10	SLP swabs, pressure tests and disinfects mains			<input type="checkbox"/>
11	Wessex Water/SLP takes bacteriological samples			<input type="checkbox"/>
12	Sample result received, passed and authorisation to proceed with the connection			<input type="checkbox"/>
13	Wessex Water to take check sample within 24 hours after connection to existing main			<input type="checkbox"/>
14	As-laid drawing provided			<input type="checkbox"/>
15	Notification of proposed mains connection		Forms <b>WWDS-SLM4 / WWDS-SLM5</b>	<input type="checkbox"/>
16	Authorisation given to SLP to proceed with the connection			<input type="checkbox"/>
17	Mains connection undertaken			<input type="checkbox"/>
18	Notification of completed/aborted mains connection submitted		Form <b>WWDS-SLM6</b>	<input type="checkbox"/>
19	Vesting certificate issued			<input type="checkbox"/>
20	Asset value of mains paid to SLP/developer			<input type="checkbox"/>